



NOTES:

1. SEE CONSTRUCTION DRAWINGS FOR PIPE SIZE, LOCATION AND INVERT ELEVATION.
2. FRAME AND GRATE SHALL BE ASTM A-36 STEEL, HOT DIP GALVANIZED AFTER CONSTRUCTION.
3. ALL CONCRETE TO BE 3300 PSI AT 28 DAYS.

LAST REVISION DATE: JULY 2015	
CONCRETE PIPE END CAP WITH GRATE (NTS)	
SILVERTON, OR	DETAIL NO. 362